

ADDENDUM 2

PROJECT NAME: FIRE STATION #24 REPLACEMENT


DATE: 08/03/2020

This Addendum 2 shall be included in and considered part of the solicitation documents for the construction of the Fire Station #24 Replacement.

RFCSP: #061720DR

DRAWINGS

Architectural



1. Sheet A3.02 Room Finish Schedule, Exercise Room 131 and Keyed Note #5: Clarification – Rubber mat flooring for Exercise Room 131 shall be 4' x 6' x $\frac{3}{4}$ " thick rubber stall mat available from Tractor Supply Co. Mats are heavy duty 100% recycled rubber. Provide interlocking mats fully covering the Exercise Room floor, glued to concrete surface.
2. Sheet A3.03 Partition Types: Clarification – It is intended that Partition Type G is a 3-5/8" metal stud smoke and sound barrier wall, STC 50 extending to roof deck.

END OF ADDENDUM 2